SWMS (Safe Work Method Statement)

Company Details:			
Installer's Company Name:	Phone Number:		
Installer's Full Name:	Mobile Number:		
Company's Address:	ABN Number:		
Project Scope:			
Scope of the work	Installation of Grid-Connect Residential Solar System		
SWMS can be used by for the limited scope as mentioned above	Installers, Electricians, Roof-workers, Project Managers		
High risk work activities covered by this SWMS.	 Person falling from more than 2 meters' height Heavy object falling from more than 2 meters' height. For e.g., Panel, Rail Electric Shock if exposed to live parts Potential Exposure to asbestos Working around/near mobile plant 		
References: Legislation, Australian Standards, Codes of Practice, SDS & SOP's	 Work Health and Safety Act / Regulation, AS/NZS 3000: Australian/New Zealand wiring rules; AS/NZS 5033: Installation of photovoltaic (PV)arrays; AS/NZS 4777: Grid connection of energy systems via inverters, And any other relevant Australian Standards and Legislation SafeWork NSW Guide to Safe Solar Panel Installation 		
Tools and equipment involved in the scope of SWMS	Edge Protection System, Ladders, EWP		
Equipment and Tools that to be maintained and checked prior to work	Vehicle (Tyres, Break, Registration etc.), Harnesses, Anchor Points, Ropes and Lanyards, First Aid kit, Low Voltage Rescue Kit, Hand/Power Tools, Voltage Tester,		

	Scaffold (when required)					
	Skylight boards/Covers (Skylight boards/Covers (when required)				
High Risk" license classes re	quired Work at Height,	Work at Height,				
for the scope of work	White Card,					
·	Electrician – Unrestricted,					
	CEC Accreditation					
	High Risk Work Licence wh	ere the EWP has the capaci	ty to reach over 11 meters			
Other Training/ Certification	n First Aid Certificate,					
	Yellow Card / Scissor Lift	or High-Risk Work Licen	se for boom type (when required),			
	Asbestos Awareness Tra	ining (when required),				
	Working Safety in the So					
Personal Protective Equipme		• • •				
	Hearing Protection,					
	Wide brimmed hats,					
	Safety Glasses, Goggles					
	Safety Hats / Shoes					
	Gloves					
	Respirator			T		
Task	Hazards	Risks to health and safety	Control measures	Who is responsible for implementing and monitoring the controls?		
Pre- start Inspection (Quick Safety Tip: Cover the skylight)	 Skylight Fragile Roof Overhead power lines Asbestos materials in roof panels Asbestos in electrical board Working over 2m Working with mobile plant, scissor lift, MEWP 	Serious injuryFatality	Please check below for in-depth control measure for each type of hazards	InstallerSite SupervisorWorkers		

•	Use of ladders		
	(For e.g., step ladders		
	and		
	platform ladders)		

(Quick Safety Tip: Ladder must be made of Fiber Glass and correctly secured at the top and bottom)

- Strong wind gust causing fall from ladder
- Falling from ladder
- Falling objects –being struck/ crushed
- Trip, slip, fall due to lose grip

- Serious Injury
- Injury to others from falling object
- Fatality in extreme situation
- Use fiber glass and industry grade ladder while working with electricity

Installer

Workers

Site Supervisor

- Must be in good working order
- Damaged ladders are removed from service.
- Ladder is secured top and bottom
- Carry ladder horizontally, not vertically
- Ensure ladders are not protruding into roads, footpaths, driveways etc. and are on firm, stable, level ground
- Set up at correct height to avoid stretching
- Maintaining 4:1 ratio
- Be aware of people working around and pedestrians
- Face ladder when ascending / descending or working from it
- Ensure 3 points of contact remain on ladder at all times, (one hand and two feet)
- Hoist tools up in a tool belt when person reaches work position
- Ensure only 1 person working from each ladder.
- Ladder extends 1m past roof edge
- Do not stand higher than the second tread below the top plate of any stepladder
- Ladders are not to be used on scaffolding or an elevating work platform to get extra height
- Must not use tools that require a high degree of leverage force which, if released, may cause the worker to over balance and fall from the ladder
- Operator of a boom-type EWP must hold a High-Risk Work Licence
- Work must be performed from within the EWP
- Workers must not stand on the handrails of the EWP
- Ensure the EWP is operated on consolidated level ground

Use of EWP
(Quick Safety Tip:
Check for overhead powerlines)

- Fall from EWP
- Overturning of EWP
- Ejected from EWP

- Serious Injury
- Fatality
- Injury to others from falling objects

•	W	or	kin	q	at	hei	iq	ht	ŀ

(Quick Safety Tip: All workers, who are working more than 2 meters high, must have Working at Height certificate.)

- Adverse weather -hot, cold, windy, wet
- Falls from a height
- Work at height above 2 meters'
- Equipment failure -Scaffold
- /trestle / ladder /EWP / harnesses etc.
- Overhead power lines

- Heat exhaustion, sunstroke, dehydration, Sunburn
- Wind gusts causing equipment failure or sudden movement resulting in fall from height causing serious injury or death
- Being struck bylightning causing burns, electrocution
- Slips, trips & falls fractures, sprains, strains

- Use an edge protection system on the working faces and applicable adjoining edges- edge protection system to comply with AS/NZS 4994- preference to be installed from ground
- Edge protection barriers, access gates must be strong enough to withstand the pressure of a person falling against it
- Use all height-access equipment as per manufacturer's instructions and for its designed purpose
- Make sure that any holes, other openings or fragile material like skylights are properly secured and covered to avoid stepping on it and falling through
- In rare circumstances, if an edge protection cannot be installed then a risk assessment must demonstrate the reasons why - Use of proper fall restraint system. Such as full body harness, with certified and load rated roof anchors in multiple locations to provide safe access and prevent worker falling
- Each anchor point should be so that the lanyard length is short enough to prevent the worker falling (fall restraint- NOT fall arrest)
- Set and maintain the lanyard length to prevent the person from reaching the edge
- Do not use rails or battens to tie the rope / lanyard
- Use correct Manual Handling techniques while placing panels
- Weather forecast is checked to ensure wet and windy conditions
- Work is not conducted in wet or slippery conditions i.e., condensation, frost, moss, rain, mould etc.
- Heat stress of workers monitored to prevent heat exhaustion.
- Set up exclusion zone below work area using cones/tape/barriers

- Installer
- Site Supervisor
- Workers

•	Solar Panel
	Installation - Grid
	Connected

(Quick Safety Tip: Only walk on safe areas)

- Plant operating
- Working near / with electricity
- Exposure to Hazardous
- For e.g., Asbestos

- Electric shock
- Electrocution
- Exposure to asbestos causing serious illness
- Follow LOTO procedures before works are conducted
- Allow sufficient time for residual/stored energy to dissipate from the assembly.
- Follow Panels and Inverter's manufacturer instructions
- Always refer and follow designer's instruction
- Only walk on safe areas
- Check for electrical lines or other obstructions when handling panels.
- Only undertake work allowed under specific license.
- Ensure works comply with electrical safety guidelines and legislation in your State/territory and AS/NZS 3000
- Switchboard in clearly and permanently marked with warning labels
- (Dual energy), location of isolation switches to solar panels, inverter unit, mains etc.
- All cables are secured and protected under Panels
- Provide user instructions to recipient of panels including a shut-down procedure
- If it is mandatory, make sure Licensed Electrical Inspector to inspect completed install
- Issue Certification of Electrical Safety upon completion.
- When conducting maintenance on panels that have been connected to the grid/power:
- Electrician to test system components and ensure they are isolated (test for dead)

- Installer
- Site Supervisor
- Workers

•	Electrical wiring
	Low voltage

(Quick Safety Tip: No live work is permitted)

- Asbestos exposure
- Electricity Energized electrical equipment / installation
- Inhalation of dust or fibers asbestos etc.
- Electrocution / Electric
- shock causing serious injury or death.
- Explosion / Fire / smoke

- LOTO (Lock out/tag out) procedures must be established. Include:
 - Shut down
 - Identify all energy sources
 - Identify all isolation points
 - Isolate all energy sources
 - De-energize all stored energies
 - Lock out all isolation points
 - Complete and attach Danger Tag and lock(s) at each isolation point

Test by "trying" to re-activate (without exposing the tester or others to risk).
While following LOTO procedures. Ensure:

- Circuit breakers, switches and combined fuse switch units are locked out
- Use locks or suitable temporary securing devices (that cannot be disrupted)
- Where isolation is done remotely, ensure all relevant conductors are bonded together and to general mass of earth at site.

On Completion:

- Test and commission the electrical installation as required
- Notify supervisor / property owner of restoration of electrical service

- Installer
- Site Supervisor
- Workers

Disturbance of Asbestos Containing Material (ACM)		 If ACM is suspected, STOP wor safe and inform home owner. Advice Sunboost installation to 	Site SupervisorWorkers
(Quick Safety Tip: Power tools not to be used on ACM)		Advice Sumboost installation te Advice homeowner to arrange asbestos removal contractor	
used off ACIM)		Make sure that roof cavity is w	ell lit
		 Carefully check presence of an creature while working in roof NOTE – If work is likely to in the disturbance of ACM, as SWMS shall be established. 	cavity volve
		ACM is removed by a compete replaced with non- asbestos co material	•
This SWMS has been developed in consultation		Power tools are not used on All	
Worker Declaration- by signing below the worker agrees t ✓ I have been consulted and have assisted in th ✓ I have been given the opportunity to comment ✓ I have read and understood how to carry out t ✓ I have been supplied with the Personal Protect	e development of this SWMS. on the content of this SWMS. he activities listed in this SWMS.	and I have been given training in the sa	fe use of these equipment.
Name of Workers	Signatures:	Add Initials	Date:
		(Ifunable to sign)	
	1	1	1

Risk Assessment Matrix

	Extreme (1)	Major (2)	Moderate (3	Minor (4)	Insignificant (5)
Almost certain	Very High	Very High	High	High	Medium
Likely	Very High	High	High	Medium	Medium
Possible	High	High	Medium	Low	Low
Unlikely	High	Medium	Low	Low	Low
Very Unlikely	Medium	Medium	Low	Low	Low

Matrix - Explained

Likelihood Description	Rating
Almost certain to occur/happen or is imminent	Almost certain
Will probably occur/happen, but not a persistent issue.	Likely
Likely to happen occasionally and has a reasonable chance of occurring.	Possible
Not expected to happen, but it is a possibility.	Unlikely
Very unlikely this will happen	Very Unlikely

Consequences	Risk Rating	Consequences	Risk Rating
 Single or Multiple Fatalities Severe injury or illness, resulting in permanent injury / disability or ill health to one or more persons Extreme stress and an inability to perform work duties in the foreseeable future You must stop working immediately and inform supervisor/manager for further risk assessment and set up adequate control measures. 	1 Extreme	 Injury or illness requiring medical or psychological treatment to one or more people Lost Time Injury (LTI) impact (less than 10 days) Significant stress and a noticeable reduction on ability to perform regular duties in the immediate future 	3 Moderate
 Major or Multiple injuries resulting in temporary disability or ill health to one or more persons Significant Lost Time Injury (LTI) impact (10 days or more) Major stress and an inability to perform work duties in the medium to long term Dangerous near miss or threat 	2 Major	 Minor injury, first aid treatment required. No lasting impact Minor concern and some reduction in ability to perform regular work duties in the short term 	4 Minor
You must stop working immediately and inform supervisor/manager for further risk assessment and set up adequate control measures.		 No treatment required No or slight concern and no impact on regular work duties. 	5 Insignificant